



UMZIMVUBU

LOCAL MUNICIPALITY

ADVERTISING DATE: 17 November 2020

UMZ/20-21/DUTYINI REPAIRS(C&CS)

SERVICE PROVIDER FOR REPAIRS OF DUTYINI MODULAR LIBRARY

Bidders are hereby invited to submit proposals/Quotations for service provider for repairs of dutyini modular library as per BoQ.

MANDATORY DOCUMENTS TO BE SUBMITTED FAILURE TO DO SO WILL LEAD TO BE NON RESPONSIVE.

Umzimvubu Local Municipality Supply Chain Management will apply. A valid Original Tax Clearance Certificate or confirmation from SARS with a verification pin, copy of company Registration/Founding Statement/CIPC Documents. Certified BBBEE certificate and a combined BBBEE for a joint venture (non-elimination item). JV Agreement for Joint venture, Minimum of 1GB CIDB grading . 80/20 evaluation criteria. Prices quoted must be firm and must be inclusive of VAT for vat vendors. Certified ID Copies of Managing Directors/ Owners. CSD Registration and MBD forms 4, 8 and 9 are compulsory submission and Billing Clearance certificate or Statement of Municipal Accounts. Certified copies of Certificates must not be later than 90 days of closing date. **No faxed, e-mailed and late tenders will be accepted.** Umzimvubu Local Municipality reserves the right not to appoint and value for money will be the key determinant. All quotation must be deposited in the quotation box situated at **Umzimvubu Local Municipality Offices at SCM office 813 Main Street, Mt Frere** not later than **12h00 noon on 24th November 2020**. All tenders must be clearly marked "Name of the project or Reference number". All service providers must be registered on CSD and submit proof. The municipality will not make award any award to a person or persons working for the state.

Enquiries: All technical enquiries may be directed to Mr. A. Mandlana & Mr Mbukushe (SCM Manager) 039 255 8500 Mbukushe.Themba@umzumvubu.gov.za

Other enquiries regarding this Bid may be directed to the office of the Municipal Manager:

Attention: Mr G.P.T Nota

813 Main Street or P/Bag X9020

MT FRERE

5090


.....
GPT NOTA (MUNICIPAL MANAGER)

Item	Description	UoM	Qty	Rate	Amount
	SECTION A				
	GENERALS				
A	Tenderers are advised to visit the site before tendering and satisfy themselves as to the nature and extent of the works, means of access to the site and availability of working space. No claims will be entertained due to the tenderer having failed to comply with these conditions.	Item	Notes		
B	The descriptions in the items are given as a guide and to assist Contractors in tendering, but are not necessarily accurate or complete. Contractors must verify the items by personal inspection on the site.	Item	Notes		
	Project Address/ Location				
C	The work to be done is at Dutyini Village in Ward 08 under EMaXesibeni town at Dutyini Primary School approximately 6km from EMaXesibeni town. The plumbing works is to be done at EMaXesibeni town in library and in municipal offices.	Item	Notes		
	Repairs of the Library				
	Unless otherwise stated; all demolished/removed work to be taken off site				
	Glazing				
1	Remove 600 x 600mm broken window panes from aluminium window frame	No	6,00		
2	Install 600 x 600 x 3mm thick clear window panes on existing aluminium window frame	No	6,00		
	LOCKS				
3	Carefully remove door lock	No	1,00		

	Solid:				
3	New three lever rebated lockset suitable for aluminium door	No.	1,00		
	Extl Air Conditioning Unit				
4	Remove damaged air conditioner external unit	no	4,00		
5	Supply and install only new 9000BTU inverter air condition outdoor unit s/s including testing for its function to condition air temperature	no	4,00		
	Support to Mobile Library Structure	m ²	18,00		
6	Jack-up mobile library structure to support it using 3 packed in 300 x 300 x 400mm high approved concrete brick to make the mobile structure to be on a same level with top landing of stair case.	No	1,00		
	<u>Ablution Facility in Mt Ayliff municipal Library and Traffic Office</u>				
	Demolition work;				
7	Brake down and remove 220mm brick wall	m ²	5		
8	Carefully remove washing basin and set aside for re-use.	No	1		
9	Carefully remove urinal mounted to wall and set aside for re-use.	no	1		
10	Carefully remove hand dryer and mounted on wall and handover to employer	No	2		
11	Carefully remove litter bin	No	1		
12	Carefully remove toiled seats with water cistern mounted to wall and set aside for re-use	No	1		

	New work;				
	Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar:				
	The following in stock bricks in (5:1) cement mortar:				
13	One brick wall	m ²	5		
	Brickwork reinforcement:				
14	115mm Wide reinforcement built in horizontally.	m	20		
	Plaster on brick wall	m ²	14		
16	30mm thick floor screed on floor in patch work	m ²	2		
	Prepare surfaces and remove all loose material, apply one coat 'Plascon Merit Plaster Primer' and two coats 'Plascon Polvin Super Acrylic' paint;				
17	On interior wall to match the existing	m ²	3		
	CERAMIC TILING				
	Prepare surface and apply adhesive cement mortar and lay ceramic floor tiles including an approved grouting colour on tiles and cleaning of the finished work to match the existing				
18	On floors	m ²	3		
19	On walls	m ²	35		
20	Close 110mm diameter hole on 220mm brick wall with concrete mortar	No	1		
	FRAMED DOORS ETC				
	Wrought meranti frame:				
21	44x90mm Wrought meranti framed framing.	m	5		

	HOLLOW CORE FLUSH DOORS				
	Hollow core flush doors with commercial veneer:				
22	40mm Door 900 x 2032mm high.	No	1		
	Locks				
	Solid:				
23	Two lever rebated lockset.	no	1.00		
	HINGES, FLOOR SPRING HINGES, BOLTS, PANIC BOLTS, ETC				
	Solid:				
24	110mm Brass hinge with nylon washers.	No	2		
	Plumbing Works				
	PIPEWORK, ETC.				
	Pipes, pipe fittings, etc.				
	WATER SUPPLIES				
	Class 2 copper pipes with straight compression fittings				
	15mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc.				
25	22mm Ditto.	m	7		
25	15mm Pipe chased into brickwork	m	15		
	Extra over copper pipes for brass compression fittings				
26	15mm Fittings.	No	3		

	SOIL DRAINAGE				
	uPVC Pipes with solvent welded straight joints including all excavation and breaking up concrete apron not exceeding 1m deep and backfill including making good in concrete apron:				
27	50mm Pipes.	m	12		
28	110mm Pipes.	m	4		
	Extra over uPVC pipes for solvent welded fittings				
	50mm Straight reducer.	No	1		
30	50mm Plain bend.	No	1		
31	110mm Plain bend.	No	1		
32	50mm Access bend.	No	1		
33	110mm Access bend.	No	2		
34	110mm Straight pan connector.	No	11		
	SANITARY FITTINGS, TANKS, GEYSERS, ETC.				
	Re installation of previous removed washing basin (labour only).	no	1		
36	Re installation of previous removed toilet seat including fixing its water cistern against the wall (labour only)	no	1		
37	Relocation installation of previous removed urinal against the wall (labour only)	No	1		
38	Medical elbow-action pillar tap, chrome. Includes: 1/4" turn ceramic disc head part, blue indice, 1/2" BSP male inlet, and flanged backnut	no	1		
	Paraplegic grab rails				

39	Full set of stainless steel grab rails pipes fixed in position against wall in paraplegic toilets	No	1		
	Provisional Sum				
	-				
	Electrical Installation				
7	Allow for R6 000,00 (Six Thousand Rand) only for the connection of electricity from classrooms to library mobile structure using 2,5mm cable installed under grounds including putting makers.	Item	1,00	R6 000,00	R 6 000,00
	SUB TOTAL				
	ADD VAT @ 15%				
	TOTAL QUOTATION				