Person dealing with this matter: Mr. Lwana

Date: 05 NOVEMBER 2013

Request for Quotation

The Umzimvubu Local Municipality invites interested service providers to provide us with quotations **TO DO PAVING OR SURFACING OF THE TRADING FACILITY PROJECT IN WARD 07 MT AYLIFF.**

Closing Date for submissions is 13/10/2013 @12:00

For any enquiries & specification, please contact Supply Chain Management Office @ tell: 039 255 8555.

NB: NO QUOTATION(S) WILL BE CONSIDERED FROM PERSON(S) IN THE SERVICE OF THE STATE. AND SUBMISSION ARE TO BE MADE AT SCM OFFICE, BBBEE VERIFICATION CERTIFICATE MUST BE ATTACHED AND A VALID TAX CLEARANCE CERTIFICATE. FURTHER MORE, NO QUOTATION(S) WILL BE CONSIDERED FROM COMPAN(Y)IES NOT REGISTERED IN THE ULM SUPPLIER DATABASE.

Mr. GPT Nota

Municipal Manager

MT AYLIFF TRADING FACILITY
PAVING WORK

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Stormwater Control				
	(a) 300mm stormwater pipe including excavation, bedding, piping and backfilling	m	30		
	(b) Stormwater cathpit / inlet to suit a 300mm dia pipe	No	1		
	(c) Stormwater outlet to suit a 300mm dia pipe	No	1		
2	Concrete Slab infront of Block A (Laundry, internet etc) and Block C				
	(a) 100mm thick Concrete slab 20Mpa/19mm including all necessary formwork	m^3	19.25		
3	Kerbing and Channeling				
	(a) Construct precast Barrier Kerb on straights and curves in excess of 4m and up to 20m radius	m	48.50		
4	Segmented Brick Paving				
	(a) Construct a layer of 20mm river Sand underneath the pavers	m^3	20.10		
	(b) Supply and lay 50 to 55mm thick segmental paving bricks or similar approved. The bricks to be laid in a herringbone pattern	m^2	1005.00		
	(c) Construct a 100mm deep x 125mm wide edge restrain block (cast-insitu concrete). Concrete to be of class 20/19 and also provide joints at 2m intervals	m^3	1.50		
			Sub-total		
			Add 14% VAT		
			TOTAL =		